



Hallandale Beach
PROGRESS. INNOVATION. OPPORTUNITY.

ADDENDUM # 11
BID # FY 2017-2018-006
CITY OF HALLANDALE BEACH S.W. DRAINAGE
IMPROVEMENT PROJECT FEMA PROJECT NUMBER 1609-75-B

Please ensure you check the City's website for the latest addendum released for this project. Below find the link to the City's website: www.cohb.org/solicitations.

Firm must provide this form signed by an authorized officer of your firm to acknowledge receipt of ADDENDUM # 11 and provide with your firm's response.

PLEASE NOTE: PLEASE DISCARD, DO NOT USE, REVISED – BID PRICE SHEET AS OF 1/16/2018.

This Bid Price Sheet has been revised.

PLEASE NOTE: REVISED BID PRICE SHEET DATED 1/24/2018. USE THIS BID PRICE SHEET.

1. The Bid Price Sheet released in Addendum #2 is no longer valid. All firms must use the following **REVISED BID PRICE SHEET DATED 1/24/2018** to submit pricing for this Bid.
2. Revisions are on the following Bid Item No. lines in red color font.
 - a. 3.02
 - b. 3.03
 - c. 3.05

REVISED BID PRICE SHEET DATED 1/24/2018

Firms must use this Price Sheet to submit your firm's Bid Price for this Project.

Firms shall hold the unit Bid prices firm throughout the contract period. Firms guarantees response time necessary to have a crew return to correct unfinished or unsatisfactory services.

The City reserves the right to increase, decrease, and/or choose the items and quantities below for the project to meet its available budget using the unit prices provided below.

Proposing firm must completely fill out each column below, unit price and total amount.

Not applicable or "N/A" is not acceptable and will cause your firm's response to be determined non-responsive.

An authorized officer of the firm per the firms Sunbiz, must sign the bid price sheet.

The award will be to the lowest responsive responsible bidder for Total Base Bid Price.

BID ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
I. GENERAL ITEMS					
Note: The percentages are based on items II thru VI.					
1.01	General Requirements - Max. 4% of items II thru VI.	1	LS	\$	\$
1.02	Mobilization/Demobilization - 2% of items II thru VI.	1	LS	\$	\$
1.03	Maintenance of Traffic - 0.5% of items II thru VI.	1	LS	\$	\$
1.04	Testing and Survey - 0.5% of items II thru VI.	1	LS	\$	\$
1.05	Prevention, Control and Abatement of Erosion and Water Pollution - 0.5% of items II thru VI.	1	LS	\$	\$
1.06	Permitting Allowance	1	AL	\$60,000.00	\$60,000.00
1.07	Record Drawings - 0.5% of items II thru VI.	1	LS	\$	\$

ADDENDUM # 11

1.08	Trench Safety, Shoring, and Security Fencing - 1% of items II thru VI.	1	LS	\$	\$
Subtotal GENERAL ITEMS					\$
II. ASPHALT OVERLAY					
2.01	1" Asphalt Type SP 9.5 Overlay	8,222	SY	\$	\$
2.02	4' Asphalt Milling	5,293	SY	\$	\$
2.03	Adjust Existing Manhole Rims	20	EA	\$	\$
2.04	Adjust Existing Valve Boxes	40	EA	\$	\$
Subtotal ASPHALT					\$
III. PAVING, GRADING, AND DRAINAGE					
3.01	18" RCP Storm Pipe (Including Backfilling, Compaction and Full-Depth Pavement Reconstruction)	213	LF	\$	\$
3.02	24" DIP Stormwater Force Main (Including Backfilling, Compaction and Full-Depth Pavement Reconstruction)	1235	LF	\$	\$
3.03	30" DIP Stormwater Force Main (Including Backfilling, Compaction and Full-Depth Pavement Reconstruction)	538	LF	\$	\$
3.04	36" DIP Stormwater Force Main (Including Backfilling, Compaction and Full-Depth Pavement Reconstruction)	357	LF	\$	\$
3.05	48" DIP Stormwater Force Main (Including Backfilling, Compaction and Full-Depth Pavement Reconstruction)	1,247	LF	\$	\$
3.06	60" DIP Stormwater Force Main (Including Backfilling, Compaction and Full-Depth Pavement Reconstruction)	95	LF	\$	\$

ADDENDUM # 11

3.07	24" DIP Forcemain Fittings (Bends, Valves, etc.)	14	TN	\$	\$
3.08	30" DIP Forcemain Fittings (Bends, Valves, etc.)	13	TN	\$	\$
3.09	36" DIP Forcemain Fittings (Bends, Valves, etc.)	8	TN	\$	\$
3.10	48" DIP Forcemain Fittings (Bends, Valves, etc.)	135	TN	\$	\$
3.11	60" DIP Forcemain Fittings (Bends, Valves, etc.)	16	TN	\$	\$
3.12	4' Diameter Storm Manhole	3	EA	\$	\$
3.13	4' Diameter Storm Catch Basin	2	EA		
3.13	24" x 37" FDOT Type C Structure	1	EA	\$	\$
3.15	Pollution Retardant Baffle	4	EA	\$	\$
3.16	48" Flap Gates	4	EA	\$	\$
3.17	72" x 90" SS Multi Disc Slide Gate	1	EA	\$	\$
3.18	Core Existing Drainage Structures	2	EA	\$	\$
3.19	Brick and Mortar Existing Manhole Connection	2	EA	\$	\$
3.20	Remove Existing Drainage Pipes (All Types)	243	LF	\$	\$
3.21	Removal and Disposal of Unsuitable Soils	2,282	CY	\$	\$
3.22	Pressure Relief Valve	1	EA	\$	\$

ADDENDUM # 11

3.23	Control Structure (Including connection to existing culvert, guardrail, sidewalk, fences, and concrete revetment)	1	LS	\$	\$
3.24	Control Structure Electrical & Standby Power System	1	LS	\$	\$
3.25	Monitoring Wells	4	EA	\$	\$
3.26	Drainage Wells (Drill Depth up to 128', BGS)	17	EA	\$	\$
3.27	Well Drilling and Casing Depth Exceeding 128'	850	VF	\$	\$
3.28	Adjust Sewer Laterals within ROW	40	EA	\$	\$
3.29	4" Concrete Sidewalk	31	SY	\$	\$
3.30	Adjust Potable Water Services within ROW	40	EA	\$	\$
3.31	4" DIP Water Main	27	LF	\$	\$
3.32	6" DIP Water Main	158	LF	\$	\$
3.33	10" DIP Water Main	201	LF	\$	\$
3.33A	Replace 20 LF of 10" Gravity Sewer Main	4	EA	\$	\$
3.34	Desilting / Water Jetting Existing Drainage Pipe	3,470	LF	\$	\$
Subtotal PAVING, GRADING, AND DRAINAGE					\$
IV.	PUMP STATION				
4.01	Pump Station Site Work	1	LS	\$	\$
4.02	Pump Station Structural Work	1	LS	\$	\$
4.03	Pump Station Mechanical Work	1	LS	\$	\$
4.04	Pump Station Raker Assembly (Funiss & Install)	1	LS	\$	\$

ADDENDUM # 11

4.05	Pump Station Electrical Work	1	LS	\$	\$
4.06	Pump Station Instrumentation Work	1	LS	\$	\$
4.07	Pump Station Standby Power System (Including 3M Wrap)	1	LS	\$	\$
Subtotal PUMP STATION					\$
V.	PAVEMENT MARKINGS AND SIGNAGE				
5.01	Pavement Markings and Signage	1	LS	\$	\$
Subtotal PAVEMENT MARKINGS AND SIGNAGE					\$
VI.	LANDSCAPING				
6.01	Existing Tree Protection & Disposition	1	LS	\$	\$
6.02	Planting & Sod Restoration	1	LS	\$	\$
6.03	Irrigation System	1	LS	\$	\$
Subtotal LANDSCAPING					\$
TOTAL BASE BID PRICE - Items I thru VI				\$	
WRITTEN TOTAL BASE BID PRICE:					

I, _____,
 Name of Authorized Officer per Sunbiz Title

of _____
 Name of Firm as it appears on Sunbiz

hereby attest that I have the authority to sign this notarized certification and certify that the above referenced information is true, complete and correct.

 Signature of Authorized Officer per Sunbiz

 Print Name

ADDENDUM # 11

PLEASE NOTE RECEIPT OF ADDENDUM # 11 BY SIGNING BELOW AND INCLUDE WITH YOUR FIRM'S SUBMISSION.

I ACKNOWLEDGE RECEIPT OF ADDENDUM # 11:

Company:	
Name:	
Title:	
Signature:	
Date:	

Sincerely,



Andrea Lues, Director, Procurement Department